

**NOTICE INVITING QUOTATION**

Sealed quotations are invited on behalf of the National Institute of Fashion Technology, from Registered Contractors of CPWD, MES & who have worked with PSU's Govt/Pvt.MNC's reputed agencies, who have carried out similar works on item rate basis as per the requirements and details as given below. The detailed bill of quantities enclosed herewith .Quotation format can be down loaded from NIFT website '[www.nift.ac.in](http://www.nift.ac.in)'.

The tenders shall be super scribed with “**Quotation for addition and alteration work in the chamber of Head (AA)**” at NIFT Campus (Head Office) Hauz Khas, New Delhi to be submitted in the tender box at 2<sup>nd</sup> floor, B- block, NIFT Campus, Hauz Khas, New Delhi by 3 P.M on 10/8/09 to be opened on the same day at 3.30 P.M. The quotation shall be accompanied with Earnest Money of Rs 1400/- in the form of demand draft/pay order payable in favour of NIFT, New Delhi.

The site can be inspected and time during working hours on any working days. No extra shall be payable for non awareness of the site conditions and constraints.

NIFT reserves the right to accept or reject any tender in part or whole without assigning any reason thereof.

**CONDITIONS**

1. The rates shall include cost of labours & material for the works complete in all respects.
2. The quoted rates shall include all taxes, duties, VAT etc. as applicable and no extra shall be payable on this account.
3. Rates shall be valid for one year from the date of work award.
4. Water and Electricity will provide free of cost at one point for bonafide use.
5. The agency must enclose copy of the PAN Card and PAN No. of the company/proprietor. Tender of any agency without above shall be rejected out rightly.
6. Agency must submit the bills within 15days of completion of work.

EARNEST MONEY	Rs.1400/-
LAST DATE OF SUBMISSION	10.8.2009
DATE OF OPENING	10.8.2009
TIME ALLOWE TO COMPLETE WORK	20 DAYS

**PE(Bldg)**

**Schedule of quantity for addition and alteration work in the chamber of Head(AA)**  
**at E-Block 3rd floor**

<b>S. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	P/F 1.0mm thick sunmica/ laminate of superior quality on wooden partition with required adhesive of required shade and colour in approved pattern as per direction of engineer -in-charge	Sqm	2		
2	P/F 19mm thick block board marked to frame ,backing or studding with screws etc complete as per direction of engineer-in-charge (frame work, packing of studding shall be paid saperaletly)	Sqm	10		
3	Providing & fixing 5.5 mm - Thick clear glass in shutters after removing the existing shutter and with suitable means of fixing at the existing cupboard .	Sqm	2		
4	Providing & fixing cup board to make additional storage including fitting/fixtute locking arrangement finishing as per requirement with following specification :	Sqm	5		

	<p>Box sides except back should be made of 19mm thick commercial board of approved quality of suitable size with depth upto 60cm. Backing is of 6mm commercial ply of ISI make with suitable beading / lipping as per requirement. Cup board should have partitions as per requirement with suitable locking arrangement i/c 125mm size handles/magnetic catchers etc. Outer surface of the cupboard shall be of sunmica /lamine finish of 1mm thick of desired colour /shade as per existing pattern fixed with adhesive and other surface should be finished with french spirit polish with coat of wooden filler as per requirement . Cup board should be made to the entire satisfaction of engineer-in-charge and as per requirement to match the existing pattern and should be fixed /hanged with suitable arrangement etc, complete.</p>				
5	Providing & fixing universal door closer of approved ISI make.	Nos	1		
6	Providing & fixing 8mm thick clear glass on table top ( Make - Modi/Saint -Gobain) with suitable rounding off the edges complete	Sqm	4		
7	Providing and laying french spirit polish on wood work( one or more coat) to give even shade	Sqm	15		
8	Floor grinding & polishing work with granite polish over the kota stone or mojaic floors (cost of shifting of furniture etc is included in the item, nothing extra is payable)	Sft	500		

9	Providing & fixing Aluminium door stopper with two leg complete	Nos	1		
10	Providing & fixing of 5.5mm thick clear glass in existing wooden door after removal of existing wooden paneling & fixing of glass in the place of panelling,complete including removal of panelling finishing as per existing shade, fixing of beading if required , labour, material etc complete to the entire satisfaction of Engineer - in -charge	Sqm	1		
	<b>Total</b>				

**Sign & Stamp of Contractor**