

NATIONAL INSTITUTE OF FASHION TECHNOLOGY, PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210

BRIEF OF QUOTATION

4758/Bldg/ExtraWork/2015

Name of work: Repairing to existing compound wall and G.I roofing of stationary shop which is

damaged due to Cyclone Nisarga at plot No.15 at NIFT, Kharghar Navi Mumbai.

	iged due to Cyclone Nisarga at plot No.15 at NIFT,	Knargr	iar Navi N	/lumbai.	
Sr. No.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm.	84.00		
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture (Compound wall 50.00+Stationery shop34.00=84)	Sqm.	84.00		
3	Providing and fixing barbed wire fencing up to 600 mm dia, including all materials laboure charges, to complete the job if required any other materials etc., complete as per direction of Engineer in charge	Rmt.	50.00		
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:	Cum.	3.00		*.
;	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all	Kg	250.0		

Seal and signature of the Agency

Date:

By Director

Date: 11/07/2020



NATIONAL INSTITUTE OF FASHION TECHNOLOGY, PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210

	T			
	complete. Fixed by welding			(4)
6	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	Kg	500.0	
7	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead.	Kg	5.00	T) X
8	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	Sqm	32.00	= 1
9	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required: 1.00 mm thick with zinc coating not less than 275 gm/m²	Sqm	32.00	
10	Repairs to existing compound wall grill work: Cutting the existing structural steel railing, removing the bends as per damaged length, straightening the bars for damaged length, angles, plates etc., welding at required places properly, drilling the holes in the concrete, fixing with nut bolts, with bars, in the compound wall so that hold the entire weight, with required/approved base plate, including priming coat at required and welded places, if any required work to complete the job, including cost of all materials, laboure charges etc., complete as per direction of Engineer in charge. (Structural steel will be paid separately)	Rmt.	40.00	

Seal and signature of the Agency

Date:

Joint Director



NATIONAL INSTITUTE OF FASHION TECHNOLOGY, PLOT NO.15 SECTOR-4, KHARGHAR, NAVI MUMBAI -410210

	GST%				
	Net Total			 	
	Total amount in words: Rupees		100000000000000000000000000000000000000		
	only				ă ,
	only	l		1 -	
Te	rms and conditions:				
1)	The quoted rates shall be valid for 60 days.				
2)	The NIFT reserves the right to accept or reject	anv qu	otation	in part or	whole without
	assigning any reason thereof.				
3)	Above rate are including GST, transportation charges.				
4)	Date of Completion of work: Within 30 days from	n the da	te of iss	ue of work	order.
5)	Payment shall be made as per the actual quant be made.	ity exec	uted, n	o additiona	l payment will
6)	No advance payment will be made.				
7)	Payment will be made after satisfactory complebill with measurement.	etion of	work a	nd submiss	ion of original
8)	Defect liability period for the work is one year (work and release of payment.	(01 year) from t	he date of	completion of
9)	5% security deposit deducted from the bill and s DLP of one year.	ame wil	l be rele	eased after	completion of
10)	The bidder may inspect the site before quoting the	neir com	petitive	rates.	
11)	To complete the work if required any additional	work sa	me will	be carry ou	at without any
	additional cost, no payment made for this purpos	se.			Maria - San See See Carlot Control of the Control o
12)	GST No: Pan No:				
13)	Copy of GST and Pan Card to be submitted along	with que	otation.		
					12
Na	me & Address of the Company:				
ING	inc & Address of the Company:				

Seal and signature of the Agency

Mobile No.:____

Date:

Joint Director