



राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, कन्नूर

(बस्त्र मंत्रालय, भारत सरकार)

National Institute of Fashion Technology, Kannur

Ministry of Textiles, Govt. of India

(An ISO 9001:2008 Certified Institute)

दिनांक/Date 10.10.2025

सूचना आमंत्रण कोटेशन(एनआईक्यू)/NOTICE INVITING QUOTATION (NIQ)

विषय: निफ्ट परिसर, कन्नूर के विद्युत उपकेंद्र में स्थापित 30 केवीए और 15 केवीए के एक-एक यूपीएस के स्थानांतरण के लिए विभाजन दीवार का निर्माण करने के संबंध में।

Sub: Construction of Partition wall for shifting of 01 No 30KVA and 01 No 15 KVA UPS installed in Electric Substation of NIFT Campus, Kannur.

निफ्ट कन्नूर, निफ्ट परिसर, कन्नूर के विद्युत उपकेंद्र में स्थापित 30 केवीए और 15 केवीए के एक-एक यूपीएस को स्थानांतरित करने के लिए सीमेंट फाइबर बोर्ड का उपयोग करके विभाजन दीवार के निर्माण हेतु प्रतिष्ठित ठेकेदारों से मुहरबंद कोटेशन आमंत्रित करता है। यह कोटेशन अनुबंध-1 में दिए गए कार्यक्षेत्र और विनिर्देशों के अनुसार है। आपसे अनुरोध है कि आप संलग्न प्रारूप में अपने आधिकारिक शीर्षपत्र पर, स्वयं, डाक या कूरियर द्वारा, निदेशक, राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, निफ्ट परिसर, मंगट्टुपरम्बा, कन्नूर-670562 के पते पर 24.10.2025 को शाम 4:30 बजे तक या उससे पहले भेज दें।

NIFT Kannur invites sealed quotations from reputed contractors for the **Construction of Partition wall using Cement fibre board for shifting of 01 No 30KVA and 01 No 15 KVA UPS installed in Electric Substation of NIFT Campus, Kannur**, as per the scope and specifications detailed in **Annexure-I**. You are requested to submit your most competitive/best rates in the enclosed format, on your official letter-head, either by hand, post, or courier so as to reach to the Director, National Institute of Fashion Technology, NIFT campus, Mangattuparamba, Kannur-670562 on or before 24.10.2025 at 4:30 PM.

निबंधन व शर्तें/Terms and conditions:

1. सभी समावेशी (कर, शुल्क, परिवहन, लोडिंग अनलोडिंग शुल्क आदि) दरें उद्धृत की जाएंगी।
All-inclusive (Taxes, duties, transportation, loading unloading charges etc) rates to be quoted.
2. आपको अनुलग्नक-1 के अनुसार कोट प्रस्तुत करना है।
You have to submit the quote as per **Annexure-I**

3. संविदाकार को यह सलाह दी जाती है कि उन्हें अपने दरों को कोट करने के पूर्व साइट पर आकर कार्य की जरूरत और स्पष्टीकरण की जांच करें यदि कोई हो तो।

Contractors are advised to visit the onsite to check the requirement of the work and clarification if any before quoting their rates.

4. आगे की स्पष्टीकरण हेतु कृपया आदर्श ए (9061801675) से संपर्क करें।

For further clarification, may please call Adarsh A (9061801675)

5. यह कार्य कार्य आदेश के जारी होने के 10 दिनों के अंदर संपन्न किया जाएगा।

The work will be completed within 10 days of issue of work Order.

6. पैन कार्ड और जीएसटी पंजीकरण सं की प्रूफ संलग्न करें।

Attach the proof of PAN card and GST registration No.

7. भुगतान 10 कार्य दिवस के भीतर भवन विभाग और वास्तविक माप के आधार पर

संतोषजनक पूर्णता के खिलाफ किया जाएगा।

The payment will be made against satisfactory completion by building department and actual measurement basis within 10 working days.

P. Chakravarthy
10/10/25

Assoc.Pro. P Chakravarthy

संयुक्त निदेशक (प्रभारी) Joint Director (I/C)

संयुक्त निदेशक / JOINT DIRECTOR

राष्ट्रीय फैशन प्रौद्योगिकी संस्थान / National Institute of Fashion Technology

दस्त्र मंत्रालय, भारत सरकार / Ministry of Textiles, Government of India

निफ्ट कैम्पस, धर्मशाला / NIFT Campus, Dharmasala

मंगलटुपम्बा, कन्नूर-६७०५६२ / Mangattuparamba, Kunnur-670562

सूची के अनुसार सूचना-पट्ट पर प्रदर्शन हेतु प्रतिलिपि:

Copy for display on the notice board as per the list:

1. Municipal Office Anthoor
2. Village Office, Morazha
3. NIFT campus Kannur Notice Board

Name of work: Partition work for shifting of 01 No 30KVA and 01 No 15 KVA UPS installed in Electric Sub station of NIFT Campus, Kannur (Civil Work)

SI No	Item Description	Unit	Quantity	Rate	Amount
1	Providing and fixing, in position concealed G.I. section for wall paneling using board of required thickness fixed on the 'W' profile (0.55 mm thick) having a knurled web of 51.55 mm and two flanges of 26 mm each with lips of 10.55 mm, placed @ 610 mm C/C in perimeter channel having one flange of 20 mm and another flange of 30 mm with thickness of 0.55 mm and web of length 27 mm. Perimeter channel is fixed on the floor and the ceiling with the nylon sleeves @ 610 mm C/C with fully threaded self-tapping dry wall screws. Board is fixed to the 'W' profile with 25 mm countersunk ribbed head screws @ 200 mm C/C., all complete as per the drawing & directions of engineer-in-charge, the joints of the boards are finished with specially formulated jointing compound and 48 mm wide jointing tape to provide seamless finish.				
	Cement fibre board of 10 mm thick, Type- B, Category- III as per IS: 14862 : 2000 reinforced with suitable fibre cement screw.	Sqm	38		
2	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.				
	30 mm thick plain PVC door shutters	Sqm	2.6		
3	Providing and fixing 125 mm bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete.	Each	2		
4	Providing and fixing bright finished brass door latch with necessary screws etc. complete : 250x16x5 mm	Each	1		
5	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 125x75x4 mm	Each	3		
6	Supplying ISI-marked heavy-duty lock, with keys.	Each	1		
7	Material and labour charge for Cutting holes of required size in masonry wall of 230 mm for passing of 50 mm pipe.	Each	6		

8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	72		
9	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	Sqm	72		
10	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. One coat	Sqm	72		
Total Amount(Rs)					
GST Amount(Rs)					
Grand Total(Rs)					
Total Amount in words:					
.....					
.....					

Supplier Name:

Signature with office seal:

Contact Number: