राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, कन्नूर
(वस्त्र मंत्रालय, भारत सरकार)
National Institute of Fashion Technology, Kannur
Ministry of Textiles, Govt.of India
(An ISO 9001:2008 Certified institute)

दिनांक/Date 19.08.2025

सूचना आमंत्रण कोटेशन(एनआईक्यू)/NOTICE INVITING QUOTATION (NIQ)

विषय: एनआईएफटी परिसर, कन्नूर में बास्केटबॉल और वॉलीबॉल कोर्ट का रखरखाव/मरम्मत
Sub: Maintenance/repair of Basketball & Volleyball courts at NIFT Campus, Kannur

निफ्ट कन्नूर, निफ्ट परिसर, कन्नूर में बास्केटबॉल और वॉलीबॉल कोर्ट के रखरखाव/मरम्मत के लिए, अनुबंध-I में दिए गए कार्यक्षेत्र और विशिष्टताओं के अनुसार, प्रतिष्ठित ठेकेदारों से सीलबंद कोटेशन आमंत्रित करता है। आपसे अनुरोध है कि आप अपनी सबसे प्रतिस्पर्धी/सर्वोत्तम दरें संलग्न प्रारूप में, अपने आधिकारिक लेटरहेड पर, स्वयं, डाक या कूरियर द्वारा, निदेशक, राष्ट्रीय फैशन प्रौद्योगिकी संस्थान, निफ्ट परिसर, मंगट्टुपरम्बा, कन्नूर-670562 को 01.09.2025 को शाम 4:30 बजे तक या उससे पहले भेज दें।

NIFT Kannur invites sealed quotations from reputed contractors for the Maintenance/repair of Basketball and Volleyball courts at NIFT Campus, Kannur, as per the scope and specifications detailed in **Annexure-I.** You are requested to submit your most competitive/best rates in the enclosed format, on your official letter-head, either by hand, post, or courier so as to reach to the Director, National Institute of Fashion Technology, NIFT campus, Mangattuparamba, Kannur-670562 on or before 01.09.2025 at 4:30 PM.

निबंधन व शर्तें/Terms and conditions:

1. सभी समावेशी (कर, शुल्क, परिवहन, लोडिंग अनलोडिंग शुल्क आदि) दरें उद्धृत की जाएंगी।
   All-inclusive (Taxes, duties, transportation, loading unloading charges etc) rates to be quoted.
2. आपको अनुलग्नक-1 के अनुसार कोट प्रस्तुत करना है।
   You have to submit the quote as per Annexure-I
3. संविदाकार को यह सलाह दी जाती है कि उन्हें अपने दरों को कोट करने के पूर्व साइट पर आकर कार्य की जरूरत और स्पष्टीकरण की जांच करें यदि कोई हो तो।
   Contractors are advised to visit the onsite to check the requirement of the work and clarification if any before quoting their rates.

4. आगे की स्पष्टीकरण हेतु कृपया आदर्श ए (9061801675) से संपर्क करें।
   For further clarification, may please call Adarsh A (9061801675)
5. यह कार्य कार्य आदेश के जारी होने के 18 दिनों के अंदर संपन्न किया जाएगा।
   The work will be completed within 18 days of issue of work Order.
6. पैन कार्ड और जीएसटी पंजीकरण सं की प्रूफ संलग्न करें।
   Attach the proof of PAN card and GST registration No.
7. भुगतान 10 कार्य दिवस के भीतर भवन विभाग और वास्तविक माप के आधार पर संतोषजनक पूर्णता के खिलाफ किया जाएगा।
   The payment will be made against satisfactory completion by building department and actual measurement basis within 10 working days.

P. Chak
19/08/25

Assoc.Pro. P Chakravarthy
संयुक्त निदेशक (प्रभारी)Joint Director (I/C)
संयुक्त निदेशक / JOINT DIRECTOR
राष्ट्रीय फैशन प्रौद्योगिकी संस्थान/National Institute of Fashion Technology
वस्त्र मंत्रालय, भारत सरकार/Ministry of Textiles, Government of India
निफ्ट कैंपस, धर्मशाला / NIFT Campus, Dharmasala
मांगाट्टुपरम्बा, कन्नूर-६७०५६२/Mangattuparamba, Kannur-670562

सूची के अनुसार सूचना-पट्ट पर प्रदर्शन हेतु प्रतिलिपि:
Copy for display on the notice board as per the list:

1. Muncipal Office Anthoor
2. Village Office, Morazha
3. NIFT campus Kannur Notice Board

(Annexure-I)

Name of work: Maintenance/repair of Basket Ball & Volley Ball courts at NIFT Campus, Kannur					
Sl No	Item Description	Unit	Quantity	Rate	Amount
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm	120		
2	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 30 cm girth upto and including 60 cm girth	Each	6		
3	Excavating, supplying, stacking and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in foundation trenches, plinth, sides of foundation etc.complete for all lift.	Cum	55		
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	Cum	20		
5	Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for foundation and plinth with thickness 15 cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	Cum	3.2		
6	20 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	Sqm	10		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	1		
8	Surface Cleaning & Preparation: Thorough cleaning of the existing surface using pressure wash, removal of dirt, moss, oil, loose particles, and laitance.	Sqm	540		
9	Crack Filling: Filling hairline and minor surface cracks using approved acrylic crack filler/putty; including grinding and finishing.	Rm	200		
10	Primer Coat: Application of one coat of acrylic primer suitable for outdoor sports coatings.	Sqm	540		
11	Base Coat (Acrylic Resurfacer): Supply and application of base coat with silica sand blend to level minor surface undulations and ensure bond with top coats.	Sqm	540		
12	Top Coat – Textured Acrylic Court Paint: Application of two coats of UV-resistant, non-slip, acrylic sports court paint (green/red/blue color as per design) including silica grit for traction.	Sqm	540		

13	Line Marking: Application of acrylic line marking paint (white) for basketball court layout with approved dimensions. Includes masking, layout, and painting.	Sqm	600		
14	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	16		
15	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	Sqm	16		
16	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats	Sqm	16		
17	Applying priming coat:With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	Sqm	14		
18	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	Sqm	14		
19	Supply and laying 4 Sq mm, 3-Core Flexible Copper Conductor PVC Cable; Make: Polycab / Finolex / KEI.	Metre	180		
20	Supply and fixing Medium Grade GI Pipe of 2inch dia.	Metre	192		
21	Supply and laying PVC conduit pipe of 20 mm dia, including all accessories.	Metre	80		
22	100W LED Flood Light with IP55 protection, Make: Havells / Bajaj / Crompton.	Each	20		
Total Amount(Rs)					
GST Amount(Rs)					
Grand Total(Rs)					
Total Amount in words:					

Supplier Name:

Signature with office seal:

Contact Number: